


## User Manual for the graphomate bubbles for Power BI



Version 2021.2 – as of May 2021

<https://www.graphomate.com>

**Table of contents**

- [Introduction](#)
- [Installation](#)
- [Quick Start](#)
- [Overview Visual Objects](#)
- [Overview Data Dimensions](#)
- [graphomate property sheet \(GPS\)](#)
- [Runtime Interactivity](#)
- [Small Multiples Mode](#)
- [Known Issues \(bubbles\)](#)
- [Known Issues \(Power BI\)](#)

## Introduction

### Meaningful portfolio analyses

Visualizations are gaining more and more importance in regards to quick and safe communication. Information presented in a simple, yet meaningful way supports deciders to find patterns and deviations. Good information design can give you a quick and efficient overview of your business. The International Business Communication Standards (IBCS) are working as a ruleset of how meaningful visualizations are used most effectively for business reporting and dash boarding.

With the graphomate bubbles we offer an additional highly configurable visualization component, which aligns itself with the IBCS concepts. The goal of the visualization is to get a **quick and easy overview of the distribution and the relationship of data points among each other**. Patterns and outliers can be recognized quickly and can be included in the interpretation and decision making.

The high density of information results from the mapping of **up to five key figures**. A two-dimensional utilization as scatterplot is possible, when two (dependent) characteristics are mapped into a chart. Of course the *graphomate bubbles* also offer many additional features you might be familiar with from other graphomate extensions. This includes a collision logic for overlapping labels, a value format configuration and optical customization.

In the following we describe the properties of the graphomate bubbles and the possibility to configure them in our user interface. This user interface is almost identical in all BI front ends - Power BI, Tableau, SAP Analytics Cloud and Lumira Designer. Formatting settings of the graphomate bubbles can be stored on the graphomate server and loaded from there, also in other BI front ends.

## Installation

### General notes on the use of graphomate extensions in Power BI


- The Power BI Report Server supports the use of graphomate extensions from version January 2020.
- The graphomate visuals must be imported for each new report if it's not provided as an organizational visual.

#### Organizational visuals


- Organizational visuals in Power BI. [Link](#) (Docu Power BI)
- Manage Power BI visuals admin settings. [Link](#) (Docu Power BI)
- The following article explains the handling and share options of visuals in the Power BI environment. [Link](#)

### Insert a graphomate visual to a report

1. To use graphomate visuals for Power BI please add it over the three points in the visualization pane-> "Import a visual from a file"




2. The graphomate property sheet (GPS) can be accessed via the three points in the upper right corner of the graphomate visual.



Your browser does not support the HTML5 video element

## Quick Start

1. If the graphomate visual is not included as an organization visual, install the visual yourself. (See Installation)
2. The icon of the graphomate visual is displayed in the visualization pane. Clicking on the icon creates the graphomate visual on the drawing canvas of the report.
3. Link the data to the visual via the fields pane. Either activate the data by activating the dimensions or key figures or assign the data to the respective data fields via drag'n'drop.
4. Settings for the graphomate visual can be made in the visualization pane, but we recommend the configuration via the graphomate property sheet (GPS).
5. The graphomate property sheet (GPS) can be reached via the three points in the upper right corner of the graphomate visual. Choose "Edit".




### Video Quickstart graphomate charts

Your browser does not support the HTML5 video element

## Overview Visual Objects

- 1 Average Customer Rating and Net Sales by Area and Budget (\$)
- 2 Customer Rating



1. Title for the diagram (may contain more than one row).
2. Series Labels, one for each data series. They are automatically generated from the data selection. The Series Labels of the data series X Axis und Y Axis (see above, Budget act. And Customer Rating) are displayed on the respective axis. They are called Axis Labels. The Series Labels for the data series Circle, Arc and Deviation (see above, Net Sales, Budget act. and Budget prev.) are displayed as a legend on the right.
3. Bubbles: The elements of this diagram are called Bubbles and represent a set of information according to the selected data series.
4. The Category Label is the label for a Bubble, which is generated from the data selection of the x axis series.
5. The Circle Label of a Bubble specify the value of its Circle Dimension, which is the data series that defines this Bubbles' area.
6. The Value Labels of a Bubble specify the values of Arc dimension (see above, grey area) and the deviation from the dimension Deviation (see above, red and green bars).

## Overview Data Dimensions

With the *graphomate bubbles* you will be able to visualize up to five data dimensions. These data series are the following.

Dimension	Description
<i>X Axis</i>	A series of values which will represent the coordinates on the x axis of the data points. The x axis represents the main dimension and serves as source for the extraction of diagram labels.
<i>Y Axis</i>	A series of values which will represent the coordinates on the y axis of the data points. The y axis represents the subordinate dimension which contains a matching value for each element of the x axis.
<i>Circle</i>	A series of values representing the area of the <i>Bubbles</i> . Setting data of this series is <u>optional</u> , but it requires the previously described series to be set. If no data is set here the chart will be drawn as a <i>Scatterplot</i> .
<i>Arc</i>	A series of values representing the area of the grey segment of each bubble (see picture below). This optional segment show the share of the corresponding value of the <i>Circle</i> series. Hence it is obligatory that the <i>Circle</i> series is set, if you want to use the <i>Arc</i> series.
<i>Deviation</i>	A series of values, also optional, which represents yet another segment of the whole circle. This segment is intended for a previous year value. This value's deviation from the <i>Arc</i> value is displayed by a red or green bar (see picture below) for a positive or negative deviation respectively. This series can only be used if the previously described series are set.






Please take care that you do not select data series with different offsets. For example, do not select the members January to June for the x axis and July to December for the y axis. You should select values of the same members for the y axis to ensure the values to match each other and the diagram labels to be extracted correctly.




## graphomate property sheet (GPS)

- Data Tab
- Labels Tab
- Bubble Elements Tab
- Axes Tab
- Scaling Tab
- Emphasis Tab
- Input Output Tab

The following usage structure can be found in all graphomate extensions with the graphomate property sheet (GPS):


<p><b>Search field</b></p> <p>Use the search field to quickly find a setting (example "Title") and change it.</p> <p><b>Connection to the graphomate server</b></p> <p> active connection to graphomate server</p> <p> no active connection to the graphomate server</p> <p><b>Info Tab</b></p> <p>In the header of the GPS there is an info symbol (  ). Click on the  icon to open a tab with relevant information:</p> <ul style="list-style-type: none"> <li>• the version number of the installed extension (important information for the support)</li> <li>• link to the graphomate Support Desk</li> <li>• to the general terms and conditions</li> <li>• to the graphomate website and</li> <li>• a list of the software libraries used (Credits)</li> </ul>	 <p>The screenshot shows the 'graphomate bubbles' header with a search bar and a toolbar. The 'Input Output' tab is active, displaying a 'Server' section with a URL field containing 'https://', a 'Save' button, and a red error indicator. Below this is the 'Info' section, which displays the version '2020.3.0', a link to 'Documentation', and the 'General Terms of Licence and Maintaining' of the graphomate GmbH. At the bottom, there is a 'Credits' dropdown menu and a 'CLOSE' button.</p>
---	---


<p><b>Checkboxes</b></p> <p>An active property is indicated by a white check mark in the checkbox. To deactivate it, click on the checkbox again.</p>	<p><b>Additional Information</b> ^</p> <p><input checked="" type="checkbox"/> Legend</p> <p><input type="checkbox"/> Tooltip</p>
<p><b>Color Picker</b></p> <p>You can enter the color value as HEX code or click on the colored circle.</p> <p>Use the Color Picker or enter color values as HEX, RGB, or HSL code. You switch between these color models using the small arrows on the right side of the color picker.</p>	<p><b>Deviations</b> ^</p> <p>Good Color <input checked="" type="radio"/> #8CB400</p> <p>Bad Color <input checked="" type="radio"/> #FF0000</p> <p><input type="checkbox"/> Invert</p> <p><b>Good Color</b></p>  <p>#8CB400</p> <p>HEX</p> <p>OK</p>

**Adding new elements to lists**

Click on the  icon to create new elements in a list.

**Removing elements from a list**

Hover over the element to delete an object. The following symbol appears . Click on the icon to delete the selected entry.

**Filter Option**

In some cases, it is necessary that several settings are only applied to certain key figures, dimensions or dimensional characteristics. You can use the filter option to define the combination to which the setting is to be applied.


In the example on the left, the desired setting is only applied to the key figure "budget". This can be, for example, a certain number formatting, a scenario or a certain icon for displaying the key figure.

Filter states can be defined in the following settings of graphomate extensions:

- graphomate matrix
  - Value Format
  - Calculations/Deviations
  - Scenario Assignment
  - Bar Chart Assignment
  - Pin Chart Assignment
  - Background Bar Assignment
- graphomate bubbles
  - Value Format
- graphomate pictograms
  - Pictograms/Icon Assignment

**Measures**

Dimension



Measures 

Members

budget x  

OK

**Copy Filter**




Filter settings on dimensions can be saved to the clipboard and reused in other graphomate extensions settings. Use the   symbols for this purpose.

**aggregation**

New Member Name  
Overall

Target Dimension  
[dropdown]



Aggregation Type  
Sum

Filter (optional)     
no items

Description (optional)  
[text area]

OK

**Input mode: Field / comma separated list (csv)**

Properties with the  symbol allow the definition of settings on the graphomate property sheet in two variants. The mode can be changed by clicking on the  symbol. The following modes are available:

1. per field: The value is entered per field. After one field has been filled, another field is created automatically.
2. As a list: The entry is made as a comma-separated list.


Example: Application of the scenarios to elements of a series (see picture)


The first series contains two forecast values (FC) and two budget values (BU). The second series contains only values from the previous period (PP). You can enter the assignment of the scenarios as follows:

Variant per field for series 1: FC (field 1), FC (field 2), BU (field 3), BU (field 4)


Variant as list for series 2: PP,PP,PP,PP,

**Scenario Assignment**

Scenarios 1   
FC FC BU BU

Scenarios 2   
PP,PP,PP,PP,

Scenarios 3  
[dropdown]



Scenarios by Series   
no items

Scenarios In Axis



Scenario Legend Enabled

Scenarios In Deviations

## Data Tab

<p><b>Data Binding</b></p> <p>Connect the data with the <i>X Axis</i>, the <i>Y Axis</i>, the circular area (<i>Circle</i>), the <i>Arc</i> and the arc segment (<i>Deviation</i>).</p>	
<p><b>License</b></p> <p><i>License Key</i></p> <p>Enter the license key here</p>	


## Labels Tab

<p><b>Title</b></p> <p><i>Titel Text</i></p> <p>Enter the title for the bubble chart in this field. Multiple-line texts are reproduced accordingly, i.e. the line break is adopted.</p> <p><i>Font Size</i></p> <p>Sets the font size of the title in [px].</p> <p><i>Padding</i></p> <p>Set the distance of the title to the diagram in [px] here.</p>	 <p>The screenshot shows the 'Labels' configuration panel. At the top, there is a search bar and a toolbar with icons for database, text (Tt), nodes, axes (Yx), legend, editing (pencil), and a list icon. Below the toolbar, the 'Labels' section is expanded to show the 'Title' configuration. It includes a checked 'Enable' checkbox, a text input field for 'Title Text', a 'Font Size [px]' input field with the value '14', and a 'Padding [px]' input field with the value '5'.</p>
<p><b>Font</b></p> <p><i>Family</i></p> <p>Define the global font. You can choose between <i>Arial</i>, <i>Tahoma</i>, <i>Lucida Console</i>, <i>Verdana</i> and <i>Calibri</i> or type in the name of a font which is installed on your system.</p> <p><i>Category Labels Size [px]</i></p> <p>Specify the size of the Category Labels in [px] here.</p> <p><i>Category Label Color</i></p> <p>Select the color for the Category Label using the color picker or by entering the HEX code.</p> <p><i>Value Label Size [px]</i></p> <p>Specify the size of the axis and element labels in [px] here.</p>	 <p>The screenshot shows the 'Font' configuration panel. It includes a 'Family' input field with the value 'Arial', a 'Category Label Size [px]' input field with the value '12', a 'Category Label Color' input field with a color picker icon and the HEX code '#666666', and a 'Value Label Size [px]' input field with the value '12'.</p>
<p><b>Value Format</b></p> <p>With the Value Format you define the way the values are displayed in the bubble chart. You access the configuration by clicking on an element in the list. You can create and define additional formats using the + symbol.</p>	Empty space for the Value Format configuration panel

Multiple Value Format Rules (Assignments) are prioritized in descending order, i.e. definitions that are lower in the list overwrite those above them when their filters overlap. Therefore, the generally valid format of the bubbles labels should be defined at the top of this list without any further filters. Value Formats defined below, restricted by filters, overwrite the formatting defined above - "From General to Special".

#### *Value Format Pop-Up*

Define the number format using the following options:



- **Locale:** Defines abbreviations, decimal and thousand separators for the respective language. You can choose between *en*, *de*, *fr* and *auto*.
- **Format Type:** Defines the type of number output. You can choose between *number* (decimal number), *percent* (percentage) and *ordinal* (ordinal number).
- **Abbreviations:** Defines the type of abbreviations for all numbers to be formatted. You can choose between *mean* (abbreviation of the mean value), *min* (abbreviation of the minimum value), *max* (abbreviation of the maximum value), *auto* (best-suited abbreviation for the respective number), *trillion* (trillion abbreviation), *billion* (billion abbreviation), *million*, *thousand* and *none* (no abbreviation at all).
- **Negative Sign:** Defines how negative numbers are displayed. You can choose between *minus*, *parenthesis*, and *none* (no sign).
- **Prefix:** The input value is placed before the number.
- **Suffix:** The input value is placed after the number.
- **Thousands Separator:** Replaces the thousand separator set by the selected *locale*.
- **Decimal Separator:** Replaces the decimal separator set by the selected *locale*.
- **Total Digits:** Defines how many digits the number may consist of. *Total Digits* is prioritized over *Decimal Digits*.
- **Decimal Digits:** Defines how many decimal places of the formatted number are displayed.
- **Scaling Factor:** The value of each data point is multiplied by the entered number to scale values.
- **Zero Format:** When the checkbox is activated, any data value equal to 0 (the number zero) is replaced by the entered value.
- **Null Format:** Any data value that equals *NULL* (no value) is replaced by the entered value.
- **Error Format:** If a data value is undefined or the result of an arithmetic error such as dividing by 0 (zero), the data value is replaced by the entered value.
- **Rounding Method:** Defines the rounding method. You can choose between *half up* (23.5 24, -23.5 -23), *commercial* (23.5 24, -23.5 -24) and *trim* (23.5 23, -23.5 23).
- **Explicit Positive Sign:** Defines whether a positive number should always be preceded by a + (plus sign).
- **Description:** Defines a description for the set configuration.

## en-US number

Locale  
en-US

Format Type  
number

Abbreviations  
auto

Negative Sign  
minus

Prefix  
\_\_\_\_\_

Suffix  
\_\_\_\_\_

Thousand Separator  
 \_\_\_\_\_

Decimal Separator  
 \_\_\_\_\_

Total Digits (approx.)  
 \_\_\_\_\_

Decimal Digits  
1

Scaling Factor  
1

Zero Format  
 \_\_\_\_\_

Null Format  
\_\_\_\_\_

Infinity Format  
∞

Rounding Method  
commercial

Explicit Positive Sign

Filter (optional) ↶ ↷ +  
no items

Description (optional)  
\_\_\_\_\_



<p><b>Additional Information</b></p> <p><i>Legend</i></p> <p>If the checkbox is activated, a legend is displayed if data has been selected for one of the fields <i>Circle</i>, <i>Arc</i> or <i>Deviation</i>.</p> <p><i>Tooltip</i></p> <p>If the tooltip is activated, the data of the respective bubble is displayed when hovering on element.</p> <div style="border: 1px solid red; padding: 5px; margin-top: 10px;"><p>In Power BI the activation of the tooltips of the graphomate bubbles is done as the following: In Power BI, in the Visualization pane, go to the Format (Formatting, paint roller symbol) symbol and choose the <i>Quick Info</i> option.</p></div>	<p>OK</p> <div style="border: 1px solid gray; padding: 10px; margin-top: 10px;"><p><b>Additional Information</b> ^</p><p><input checked="" type="checkbox"/> Legend</p><p><input type="checkbox"/> Tooltip</p></div>
---	--

## Visibility

### Circle Labels

Switches the *Circle Labels* permanently on (*Always*), off (*Never*) or leaves the decision to the collision logic (*Auto*). In *Auto* mode, *Circle Labels* are hidden in case of collision. *Circle Labels* have higher priority than *Value Labels*, but lower priority than *Category Labels* or other bubbles. This order is applied accordingly in the collision logic.

### Arc and Deviation Labels

Defines whether the values of the deviations and arc segments should be displayed.

### Category Labels

Switches the *Category Labels* permanently on (*Always*), off (*Never*) or leaves the decision to the collision logic (*Auto*). In *Auto* mode, *Circle Labels* are hidden in case of collision. *Circle Labels* have higher priority than *Value Labels*, but lower priority than *Category Labels* or other bubbles. This order is applied accordingly in the collision logic.

### Axis Labels

Sets whether the *Axis Labels* are displayed or hidden.

Label visibility priority (from high to low) for collisions:

- Category Labels
- Circle Labels
- Arc and Deviation Labels

## Visibility

### Circle Labels

always auto never

Arc and Deviation Labels

### Category Labels

always auto never

Axis Labels

**Manual Series Labels**

At this point, strings can be assigned for the data series. The checkboxes activate the manually set label, otherwise the automatically generated labels are used.

The *Manual Series Labels* are also used for the legend.

**Manual Series Labels** ^

X-Axis

 X-Axis

Y-Axis

 Y-Axis

Circle

 Circle



Arc

 Arc

Deviation

 Deviation

## Bubble Elements Tab

<p><b>Styling</b></p> <p><i>Circle Color</i></p> <p>Here you can set the color of the circle area line by clicking on the corresponding color field or by entering a HEX code.</p> <p><i>Arc Color</i></p> <p>Here you can set the color of the arc by clicking on the corresponding color field or by entering a HEX code.</p> <p><i>Fill Circle</i></p> <p>If <i>Fill Circle</i> is activated, the area of the circle is filled with the <i>Circle Color</i>.</p>	 <p>The screenshot shows the 'graphomate bubbles' application interface. At the top right, there are icons for Wi-Fi and information. Below the header is a search bar. A row of navigation icons includes a database symbol, 'Tt' for text, a bubble chart, a coordinate system (Y, X), a vertical bar chart, a pencil for editing, and a list icon. The 'Bubble Elements' panel is open, showing the 'Styling' section with a blue circle icon, a color field set to '#007CC1', a grey circle icon, a color field set to '#BBBBBB', and a 'Fill Circle' checkbox.</p>
<p><b>Deviations</b></p> <p><i>Good Color</i></p> <p>Here you can set the colors for positive (<i>Good Color</i>) connected deviations by clicking on the corresponding color field.</p> <p><i>Bad Color</i></p> <p>Here you can set the colors for negative (<i>Bad Color</i>) connected deviations by clicking on the corresponding color field.</p> <p><i>Invert</i></p> <p>If the checkbox <i>Invert</i> is activated, positive deviations are evaluated as negative and thus get the color for negative deviations (and vice versa).</p>	 <p>The screenshot shows the 'Deviations' section of the 'Bubble Elements' panel. It features a green circle icon, a color field set to '#8CB400', a red circle icon, a color field set to '#FF0000', and an 'Invert' checkbox.</p>
<p><b>Conditional Formatting</b></p> <p><i>Configuration</i></p> <p>This configuration allows the appearance of the bubbles to be adjusted based on conditions. With a click on the +- symbol a dialog opens in which the conditions is defined,</p> <p><i>Configuration Pop-Up</i></p>	

For each bubble, the value from the selected series (*Source*) is compared with the operand(s) (*Operator*). If the condition applies, the selected (optical) *Effect* is applied. Depending on the selected *Operator*, between none and 2 operands must be selected.

- *Description*: Enter the name of the condition here.
- *Operator*: Defines the condition for comparing the value with the operand(s).
  - *equal*: Is the value equal to the operand?
  - *not equal*: Is the value not equal to the operand?
  - *less*: Is the value smaller than the operand?
  - *less or equal*: Is the value smaller or equal to the operand?
  - *greater*: Is the value greater than the operand?
  - *greater or equal*: Is the value greater or equal to the operand?
  - *between*: Is the value between the two operands?
  - *not between*: Is the value not between the two operands?
  - *always*: The effect is always applied regardless of the data.
  - *contains*: Does the value contain the operand? (for *Labels*)
- *Source*: Determines with which data series the operand or operands are compared.
  - *x*: The data value from which the position of the bubble on the X-axis results.
  - *y*: The data value from which the position of the bubble on the Y-axis results.
  - *circle*: The data value from which the area of the bubble results.
  - *arc*: The data value from which the area of the circular arc of the bubble results.
  - *dev*: The data value from which the deviation circle section of the bubble results.
  - *label*: The caption shown below the bubbles.
- *Value*: Determines with which values are going to be compared to the values from the data series.
  - *Value 1*: Not required for *Operator always*.
  - *Value 2*: Not required for operator always, contains, >=, >, <=, <, != and =
- *Effect*: Is applied if the condition is evaluated positively.
  - *circle color*: Changes the fill color of the circle.
  - *stroke color*: Changes the color of the circle border.
  - *stroke width*: Changes the thickness of the circle border.
  - *css class*: Adds the specified CSS class.

**Conditional Formatting** ^

Configuration +

circle-less: 10000

circle-less: 10000

Enable

Description

Operator

less

Source

circle

Value 1

10000

Value 2

Effect

circle-color

Characteristic

#FF0000

OK

- **Characteristics:** Depending on which effect was defined, the following values can be stored
  - *circle color:* HEX code of a color.
  - *stroke color:* HEX code of a color.
  - *stroke width:* An integer that represents the line width in [px].
  - *css class:* Here you define the CSS class to be used.

### Troubleshooting

#### *Performance Limit*

Sets the limit for the maximum number of bubbles up to which no performance problems occur. Using values greater than 100 is not recommended. If the limit is reached, a performance-optimized display is used for the bubbles. Only the X and Y dimensions are used here. The individual data points are displayed transparently, so that accumulations of data points appear darker and therefore focal points can be recognized. To identify outliers, a tooltip is displayed when moving the mouse over a bubble.

#### *Draw Boundaries*

This option is intended for test purposes. If it is activated, its limits are drawn for each element. These boundaries are used by the collision logic to hide overlapping labels.

### Troubleshooting

Max Bubble Count

100

Draw Element Boundaries

## Axes Tab

### Fixation

You can use the *Start of X/Y Axis* option to have the scaling of the axis start at 0 or any other arbitrary value. Similarly, you can use the *End of X/Y Axis* option for the corresponding axis to let the scaling of the axis end at any value.

The screenshot shows the software interface for 'graphomate bubbles'. At the top, there is a search bar and a toolbar with icons for database, text, network, axes, zoom, edit, and print. The 'Axes' tab is selected and expanded, showing a 'Fixation' section with four options, each with a checkbox and a text input field:

- Start of X-Axis  
0
- End of X-Axis  
0
- Start of Y-Axis  
0
- End of Y-Axis  
0

### Guides

To highlight threshold or target values, the so-called *Guides* can be added, whose appearance can be extensively customized.

#### Guides Pop-Up

With the + button *Guides* definitions can be added. The following options are available for each guide:

- *Description*: Enter the name of the guide here.
- *Value*: Defines the position of the guideline on the axis. If the character string *mean* is entered instead of a numerical value, the average of the data series on which the axis is based is taken as the value.
- *Color*: Opens the Color Picker to select a color for the line or defines the color using HEX code.
- *Width [px]*: Sets the width of the guideline in [px].
- *Label*: Are displayed on the axis at the position of the guideline. If *auto* is defined for the label, the line is provided with a label corresponding to the axis value at the position. If *none* is defined for the label, no label is displayed. Any other inserted text is displayed as label.
- *Bold Label*: Bestimmt, ob das Label Fett gezeichnet wird.

### mean

Enable

Description

Value

mean

Color

#000000

Width [px]

2

Label

auto

Bold Label

OK

### Basic Grid Lines

#### Segments

If segments are deactivated, no *Grid Lines* of the coordinator system are drawn.

#### Border

When Border is activated, a frame is always displayed around the coordinate system.



### Custom Grid Lines

It is possible to display additional lines in the grid. These are defined either by the size of the intervals (*Interval*) or the number of steps (*Steps*). The size of the intervals describes the line distance in the unit of the respective axis. The number of steps defines how many parts the respective axis consists of. For a meaningful representation the feature *Segments* should be deactivated.

### Custom Grid Lines ^

Interval X-Axis

0

Interval Y-Axis

0



Steps X-Axis

0

Steps Y-Axis

0

## Scaling Tab

<p><b>Layout</b></p> <p><i>Draw Full Segments</i></p> <p>If the <i>Full Segments</i> checkbox is activated, the scaling of the axes is selected so that all quadrants of the grid have the same size. If it is deactivated, the axes are scaled so that the available space is optimally used. However, half quadrants may be created. For optical reasons, the outer lines of the grid (<i>Borders</i>) at the top and right are hidden.</p> <p><i>Padding</i></p> <p>Set a distance in [px] for the padding that surrounds the entire diagram.</p> <p><i>Reserve Space for Hidden Labels</i></p> <p>If Reserve Space for Hidden Labels is activated, the scaling is selected so that all bubbles including their labels fit into the diagram. This also includes labels hidden by collision.</p> <p><i>Reserve Space for Annotations</i></p> <p>If Reserve Space for Annotations is activated, the distance of the axes from the edge of the component is selected so that all axis labels can be displayed. This particularly includes annotations that are displayed on the axis due to runtime interactivity and represent the value of a bubble.</p> <p><i>Collision Adjustment Factor</i></p> <p>Use the Collision Adjustment Factor to define a value in [px] that specifies by how many pixels labels may overlap each other until they are hidden by the collision logic.</p>	 <p>The screenshot shows the application window with the 'Scaling' tab selected. The 'Layout' section is expanded, showing the following settings:</p> <ul style="list-style-type: none"> <li><input checked="" type="checkbox"/> Draw Full Segments</li> <li>Padding [px]: 10</li> <li><input type="checkbox"/> Reserve Space for Hidden Labels</li> <li><input type="checkbox"/> Reserve Space for Annotations</li> <li>Collision Adjustment Factor [px]: 3</li> </ul>
<p><b>Circles</b></p> <p><i>Absolute Values</i></p> <p>If this option is activated, the amount for each value of the Circle series is calculated and used as the data basis for the display. This is useful if negative values occur in the selection that should actually be displayed as positive.</p> <p><i>Min and Max Radius [px]</i></p> <p>Define the upper and lower limits for the radius of the bubbles in [px]. This means that no bubble with a radius greater or smaller than the min. or max. radius exists.</p>	 <p>The screenshot shows the application window with the 'Circles' tab selected. The 'Circles' section is expanded, showing the following settings:</p> <ul style="list-style-type: none"> <li><input type="checkbox"/> Absolute Values</li> <li>Min Radius [px]: 5</li> <li>Max Radius [px]: 42</li> </ul>

**Zoom**

Four different zoom modes can be selected. You can choose between *none*, *rect*, *magnify* and *scale*.

**Zoom**

none selection magnify scale

## Emphasis Tab

### Emphasising

#### *On Hover*

With this option, certain bubbles can be highlighted directly without moving the mouse over them.

#### *Category Emphasis*

A bubble is selected based on a portion of the contents of the category label. Several selectors are possible simultaneously. The entry is made per field or as comma-separated notation.

For example, if the cardinal point is part of the category label and all bubbles from west and north are to be highlighted, the value of the property would be as follows: North,West

#### *Opacity of other Bubbles*

This value determines to what extent bubbles that are not highlighted should be hidden. The value starts at 0.0 (completely hidden) and ranges up to 1.0 (completely visible).

#### *Annotations*

If this option is activated, *Annotations* are displayed at runtime when the mouse is moved over a bubble. Annotations are temporary labels that are connected to the bubble by lines and represent the respective value on the axis.

The screenshot shows the 'graphomate bubbles' application interface. At the top, there is a search bar and a toolbar with icons for database, text, scatter plot, axes, zoom, edit, and print. Below the toolbar, the 'Emphasis' settings panel is open, displaying the following options:

- Emphasising** (checked)
- On Hover
- Category Emphasis `CSV`
- Fade Out Opacity:
- Annotations

## Connection

### *Related Bubbles*

If this feature is enabled, bubbles are connected in the order in which they appear in the data. This can be used, for example, to display temporal progressions or to mark the assignment of bubbles to each other more clearly. How bubbles are assigned to each other is defined by the *Matcher Index*. Redundant elements in the *Category Label* are hidden if possible and only displayed at the first element.

### *On Hover*

Determines whether the bubbles should be connected initially, or (if this option is activated) as soon as a bubble is highlighted with the mouse.

### *Matcher Index*

This index defines how bubbles should be assigned to each other. The value -1 means that all bubbles are connected to each other. All values from 0 to n define the position of the category label of the element to be assigned. For example, if there are two bubbles, the first one has the category label "*South, Internet*" and the second one "*South, Computers*" and you want to assign all bubbles from the south to each other, select index 0 to use the first element of the category label.

## Connection

Related Bubbles

On Hover

Category Matcher Index

-1

### Ranges

*Ranges* can be added to highlight complete areas of the X or Y dimensions. This is done by clicking on the +-symbol. Alternatively, one of the existing sample definitions can be activated and adjusted. The *Ranges* are divided into areas that should be marked on the X- or Y-dimensions. The checkbox in front of the definitions activates the respective range. Furthermore the following options are available:

- *Enabled:* (De)Activates the Range.
- *Description:* Descriptions can be inserted here.
- *Start:* Defines the position as data value where the *Range* should start. Instead of a numerical value, the following wildcards are available: *min*, *mean* and *max*. This defines the minimum, average or maximum of the respective data series as the starting point of the Range.
- *End:* Defines the position as a data value at which the *Range* should end. Instead of a numerical value, the following wildcards are available: *min*, *mean* and *max*. This defines the minimum, average or maximum of the respective data series as the end point of the Range.
- *Opacity:* Sets the transparency of the Range in values from 0 (completely transparent) to 1 (not transparent).
- *Color:* Sets the color of the range.

#### Ranges

X-Axis +

500-1000

Y-Axis +

500-1000

### 500-1000

Enable

Description

Start

500

End

1000

Opacity

0.5

Color

#999999

OK

### Trend

The checkbox activates the trend line. It is intended to visualize the trend of the development of the displayed data points and to make connections recognizable. This line is the regression line known from statistics, which represents the linear relationship of values in a Cartesian coordinate system. The following options are available:

- *Color:* Determines which color the trend line should have.
- *Width [px]:* Defines the width of the trend line.
- *Correlation:* Activates the display of the correlation coefficient under the legend of the bubbles. This indicates how precisely the course of the trend line can be determined. The value varies between 1 (absolutely accurate trend line) and 0 (trend line not meaningful).

#### Trend

Enable

Color

#0000FF

Width [px]

2

Correlation

## Graphs

For orientation in the coordinate system, various graphs can be added according to their function and then drawn. This is done by clicking on the + button. Alternatively one of the existing sample definitions can be activated and adapted. The checkbox in front of the definitions activates the respective graph. Furthermore the following options are available:

- *Enabled:* (De)Activates the graph.
- *Description:* Descriptions can be inserted here.
- *Function:* The function that determines the appearance of the graph. They can be written following the specifications of [expr-eval](#) and depend on the variable  $x$ . For example  $x$ ,  $x^2$ ,  $\sin(x)$ ,  $\sqrt{x}$ ,  $\log(x)$ .
- *Color:* The color of the line of the graph.
- *Width:* The width of the line of the graph in pixels.

### Graphs

Definitions +

$x^2$

---

$x^2$

Enable

Description

Expression

$x^2$

Color

#000000



Width [px]

2

OK

## Input Output Tab

The functions of this tab are used to exchange templates for the graphomate bubbles. Connect to the graphomate server - a free component of graphomate GmbH - to store or load a graphomate bubbles template. This way you can exchange preconfigured graphomate bubbles designs between BI frontends that support the graphomate server. These are currently Power BI, Tableau, SAP Analytics Cloud, SAP Lumira Designer and SAP Web Intelligence.

<p><b>Server</b></p> <p>Here you enter the URL of the graphomate server to which the component should connect and from which you want to save or retrieve templates.</p> <p>If you have entered the URL to the server, a green check mark indicates that a connection could be established.</p> <p>If another server is used later, the button next to the save button can be pressed and the server URL can be edited.</p> <p>The hyperlink "<i>Admin</i>" allows you to jump to the admin area of the graphomate server.</p>	
<p><b>Templates</b></p> <p>If the current settings are to be saved as a template, a new template name can be entered in the input field labeled <i>Create Template</i> and confirmed by clicking the <i>Save State</i> button. If the entered name complies with the naming convention, the template is saved on the server and a toast with the corresponding message is displayed in the lower part of the <i>graphomate property sheet</i>.</p> <p>However, if the entered name does not meet the expected naming conventions, an error message with the permitted characters is displayed accordingly.</p> <p>With <i>Choose Template</i> templates stored on the server can be retrieved and applied. To do this, the desired template must only be selected and the <i>Apply</i> button must be pressed. If you want to delete a template, you have to select the template in the list and press the <i>Delete (bin symbol)</i> button. If changes have been made to the templates on the server side, you have to click on the <i>Refresh</i> button. Changes should then be visible.</p>	



## Runtime Interactivity


- [Hover](#)
- [Clustering](#)
- [Zoom Modi](#)

## Hover

### Highlight on Hover

The *graphomate bubbles* provide the functionality to selectively show all the information associated with a single *Bubble*. To highlight a data point use your mouse to hover over a single *Bubble*. Now all the values, labels and annotations will be displayed. This state can be fixed with **CTRL+Click**. If the *Connection - Related Bubbles* and *Connection - Bubbles On Hover* options are activated, all associated bubbles will also be highlighted and the connection will be displayed sequentially.


Average IMDb Rating, worldwide Gross by Genre and Budget (\$) studio 90, 2016




## Clustering

### Clustering


Depending on the data set, Bubbles can be drawn with the same X and Y position and the same radius. The accumulations of bubbles are then characterized by the fact that they lack any labeling and the border is drawn thicker.



If the mouse is hovered over such a **Cluster** of bubbles, the underlying bubbles fan out aside. The front bubble is displayed completely including their labels.



If one of the fanned bubbles is now hovered, this one is brought to the foreground and displayed in the correct (original) position with its labels.



## Zoom Modi

### Zoom-Modi


The following four zoom modes Rectangular Selection, Rectangular Section, Magnification and Scaling Adjustment can be set in the graphomate property sheet in the tab *Scaling* under **Zoom**.

The selection **None** and **Selection** both activate the rectangular selection, whereby **Selection** only displays the previously selected sections on the axes, **Magnify** the magnification and **Scale** the scaling adjustment.

Die Auswahl **None** und **Selection** aktivieren beide jeweils die Rechteck-Selektion, wobei bei *Selection* auf den Achsen nur noch die vorher selektierten Abschnitt dargestellt werden, **Magnify** die Vergrößerung und **Scale** die Skalierungsanpassung.


### None

At runtime it is possible to select a set of bubbles in rectangular form using click&drag.




### Rectengular Selection


The rectangle selection behaves exactly like the **None** setting.



In addition, after the selection has been made (release the mouse button), the scaling is changed.




This way, only the bubbles that are located in the selected area are displayed.




### Magnification

A section of the bubbles can be enlarged by means of the mouse wheel (scrolling).






The point at which the magnification is directed is determined by the position of the mouse pointer.




In addition, the displayed section can be moved by drag & drop



### Scale Adjustment

This mode is similar in operation to the **Magnification** mode, i.e. using the mouse wheel (scrolling) and Drag&Drop. The scaling of the axes is then adjusted so that only a section of the bubbles is displayed. This section is determined by the position of the mouse pointer.



The displayed section can be moved by drag & drop.



For technical reasons, this mode is more complex and thus consumes more resources while expanding. As a result, too many bubbles lead to a delay in drawing. Internet Explorer also leads to a noticeable slowdown.

## Small Multiples Mode

To draw a Scatter- or Bubble-Diagram Data for the X- and the Y-Axis is necessary to be set in correlation. If one or both of these measures is missing, an alternative mode will be used to draw the Bubbles. The so called *Small Multiples Mode*.



In this mode all data points will be drawn sorted by the *Circle-Measure* from high to low in small tiles. If there are too many data points to be drawn, the smaller ones will be summarized in the *Rest* tile.

Some options and features that are usable in the normal mode are deactivated while the Bubbles are in *Small Multiples Mode*.

## Known Issues (bubbles)

### Tooltips in Power BI

- Tooltips are enabled in Power BI (Web and Desktop) on the *Visualizations pane* in the *Format pane* (color scroll icon) under "*QuickInfo*".
- The number formatting in the tooltips cannot be modified.

## Known Issues (Power BI)

- Not supported
  - PDF Exports
  - own CSS classes
  - global scenarios, must be created for each graphomate visual (alternatively retrieve the definition via the graphomate server)
  - scripting
- In order to copy a graphomate visual, it's necessary to select the border or the title of the visual.